

BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of work: Detailed Estimate for the Work of Improvements to Road and Drains at Jakkur in Ward No.05, Byatarayanapura Sub Division


		Estimate Cost Rs.						2000000.00	
SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD SR 2014-15	cum							
	Desilting of Drains								
	Jakkur Govt School Road		2	300.00	0.40	0.35	84.00		
	Post Office Road		2	165.00	0.40	0.35	46.20		
	Burm Cutting								
	Jakkur Govt School Road		2	300.00	0.90	0.30	162.00		
	Post Office Road		2	165.00	0.90	0.30	89.10		
							381.30	146.88	56005.00
	Basic Rate	136.00							
	Area Weightage @ 8%	10.88							
	Total	146.88							
2	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(b) / 2.3.5,P No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum							
	For Culverts		4	6.50	1.95	1.05	53.24		
							53.24	264.60	14086.00
	Basic Rate	245.00							
	Area Weightage @ 8%	19.60							
	Total	264.60							
3	Removing B.S Slab of Drain and stacking Page No.25/ Item No. 5.32/ PWD SR 2014-15	Sqm							
	Jakkur Govt School Road		2	300.00	1.35		810.00		
	Post Office Road		2	165.00	1.35		445.50		
							1255.50		
	Deduct 30% Missing Slabs						376.65		
							878.85	58.32	51255.00
	Basic Rate	54.00							
	Area Weightage @ 8%	4.32							

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	Total	58.32							
4	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 25/ Item No. 5.33/ PWD SR 2014-15	Sqm							
							Qty Vide Item No.3	878.85	
							878.85	75.60	66441.00
	Basic Rate	70.00							
	Area Weightage @ 8%	5.60							
	Total	75.60							
5	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick Page No.25/ Item No. 5.31.1/ PWD SR 2014-15	Sqm							
	For Missing slabs (30%)						Missing Slabs	376.65	
							376.65	639.36	240815.00
	Basic Rate	592.00							
	Area Weightage @ 8%	47.36							
	Total	639.36							
6	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2014-15	Cum							
	For Culverts		4	6.50	1.95	0.15	7.61		
							7.61	4847.04	36862.00
	Basic Rate	4488.00							
	Area Weightage @ 8%	359.04							
	Total	4847.04							
7	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2014-15	cum							
	For Culverts		4X2	6.50	0.60	0.45	14.04		
							14.04	3836.16	53860.00
	Basic Rate	3552.00							
	Area Weightage @ 8%	284.16							
	Total	3836.16							

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
8	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No.23/ Item No. 5.9/ PWD SR 2014-15	Sqm							
	For Culverts		4X2	6.50	0.50	0.45	11.70		
							11.70	4542.48	53147.00
	Basic Rate	4206.00							
	Area Weightage @ 8%	336.48							
	Total	4542.48							
9	KSRB 4-6.7 : Providing and removing centering , shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.34/ PWD SR 2014-15	Sqm							
	For Culverts		4	6.50	0.60		15.60		
	For Sides		4X2	6.50	0.23		11.96		
			4X2	1.65	0.23		3.04		
							30.60	260.28	7964.00
	Basic Rate	241.00							
	Area Weightage @ 8%	19.28							
	Total	260.28							
10	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth , including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2014-15	cum							
	For Culverts		4X2	6.50	0.50	0.10	2.60		
	Vent Bed		4	6.50	0.60	0.10	1.56		
							4.16	5287.68	21997.00
	Basic Rate	4896.00							
	Area Weightage @ 8%	391.68							
	Total	5287.68							
11	KSRB 15.1.3: Providing Flush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2014-15	Sqm							
	For Culverts		4X2	6.50		0.50	26.00		

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
							26.00	91.80	2387.00
	Basic Rate	85.00							
	Area Weightage @ 8%	6.80							
	Total	91.80							
12	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2014-15	Cum							
	For Culverts		4	6.50	1.65	0.23	9.87		
							9.87	6065.28	59846.00
	Basic Rate	5616.00							
	Area Weightage @ 8%	449.28							
	Total	6065.28							
13	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2014-15	Tone							
	0.080 Qtl/Cum		0.08	9.87			0.79	78351.84	61848.00
	Basic Rate	72548.00							
	Area Weightage @ 8%	5803.84							
	Total	78351.84							

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
14	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406,P No. 154/ Item No. 20.18/ PWD SR 2014-15	Cum							
	Jakkur Govt School Road		1	300.00	5.00	0.15	225.00		
	Post Office Road		1	165.00	4.50	0.15	111.38		
							336.38	1438.56	483896.00
	Basic Rate	1332.00							
	Area Weightage @ 8%	106.56							
	Total	1438.56							
15	KSRRB 500-4: providing and applying primer coat from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications Do- Medium Porosity MORTH chapter 5, No. 175/ Item No. 21.4/ PWD SR 2014-15	Sqm							
	Jakkur Govt School Road		1	300.00	5.00		1500.00		
	Post Office Road		1	165.00	4.50		742.50		
							2242.50	74.52	167111.00
	Basic Rate	69.00							
	Area Weightage @ 8%	5.52							
	Total	74.52							
16	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. P. No. 174/ Item No. 21.20/ PWD SR 2014-15	Cum							
	Jakkur Govt School Road		1	300.00	5.00	0.025	37.50		



ಸಹಾಯಕ ಅಭಿಯಂತರರು
 ಸಿ.ಎಂ.ಪಿ. ಬಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

Assistant Executive Engineer
 Byatarayanapura Sub Division
 B.B.M.P. Bangalore-24